

Er. G.PRADEEP, B.E.,(Civil), MBA, DLT

Licensed Surveyor

**PG BUILDERS & CONTRACTORS**

92, Saliyar Street, Muhavoor,

Virudhunagar Dist - 626111

CELL: +91 9940269862

EMAIL: pgbuilders2015@gmail.com

---

ABSTRACT ESTIMATE COST FOR THE RENOVATION WORK OF SCHOOL BUILDING NAMED SHAARON  
SPECIAL SCHOOL LOCATED AT KALANGAPERI ROAD, RAJAPALAYAM

FOUNDER: Mrs. T. PREMA

IT IS A RCC (1:2:4) FRAMED STRUCTURE

ESTIMATED AMOUNT –RS. 7,90,000/-

(RUPEES SEVEN LAKHS AND NINTY THOUNSAND ONLY)

RAJAPALAYAM

27.08.2021

  
**G. PRADEEP, B.E.(CIVIL), MBA, DLT**  
Licensed Surveyor & Contractor,  
297, Sivakamipuram Street,  
RAJAPALAYAM - 626 117.

# Quotation - Construction.

S.No	DESCRIPTION OF WORKS	NOS	LENGTH	BREADTH	DEPTH	QUANTITY	RATE	AMOUNT
			FT	FT	FT	SQ.FT (OR) CFT		
1	<b>PLASTERING</b>							
	Plastering Inner wall	2	13.25		11	291.5		
		2	14.5		11	319		
		2	13		11	286		
		2	13.25		11	291.5		
		1	20		9	180		
		1	20		9	180		
		1	5		9	45		
	Ceiling Plastering	1	13.25	14.5		192.1		
		1	13	13.25		172.3		
	Loft	2	13.25	2		53		
		2	11	2		44		
		2	11	2		44		
		2	4	2		16		
		2	13.25	4		106		
		2	14.5	2		58		
		2	13.25	2		53		
	Outer sun shade	2	8	2		32		
		2	34	2		136		
		2	5	1		10		
		2	5	1		10		
		2	5	1		10		
		2	20	2		80		
	Parapet Wall Plastering	1	34		3	102		
		1	20		3	60		
	Outer Plastering							
		1	20		9	180		
		1	34		17.5	595		
		1	30		14	420		
						3966.4	45	178488
2	<b>TILES WORK</b>							
	Floor	1	13.25	14.5		192.1		
		1	13	13.25		172.3		
	Wall	2	13.25		7	185.5		
		2	14.5		7	203		
		2	13		7	182		
		2	13.25		7	185.5		
						1120.4	110	123244
3	<b>Filling with Gravel</b>	1	23	24	2	1104		
		1	20	5	2	200		
						1304	15	19560
4	<b>CEMENT FLOORING</b>	1	23	24		552		
		1	20	5		100		
						652	60	39120
5	<b>WATER TANK</b>							
	Excavation	1	10	8	6	480	15	7200
	Flooring	1	10	8		80	50	4000
	Brick Work	2	11.5		6	138	150	20700
		2	8		6	96	150	14400
	Plastering	2	10		6	120	40	4800
		2	8		6	96	40	3840

  
**CORRESPONDENT**  
**SHAARON SPECIAL SCHOOL**  
**RAJAPALAYAM.**

	Concrete	1	11.5	9.5		109.3	200	21850
								76790
6	<b>COMPOUND WALL</b>							
	Compound wall Brick work	1	23		2	46.0	150	6900
	Plastering	2	23		2	92.0	40	3680
								10580
7	<b>GRILL WORK</b>							
	Grill Work	1	10		8	80.0		
		1	5		5	25.0		
		1	5		3	15.0		
						120.0	300	36000
8	<b>WOOD WORK</b>							
	Wood Window	1	4.5		3	13.5		
		1	3		4	12.0		
		2	3		3	18.0		
	Wood Door	1	4		7	28.0		
		1	3		7	21.0		
		1	3		7	21.0		
		1	3		7	21.0		
	Attach Window	1	3		4	12.0		
						146.5	600	87900
9	<b>WEATHERING COURSE</b>	1	34	20		680.0	100	68000
10	<b>SS WORK</b>	1	24			24.0	1000	24000
11	<b>ELECTRICAL</b>				LS			40000
12	<b>PLUMBING</b>				LS			25000
13	<b>INTERIOR WOOD WORK</b>				LS			60000

*Pradeep*

**G. PRADEEP, B.E.(Civl), MBA, DLT**  
**Licensed Surveyor & Contractor,**  
**297, Sivakamipuram Street,**  
**RAJAPALAYAM - 626 117.**

**ABSTRACT ESTIMATE COST FOR THE RENOVATION WORK OF SCHOOL BUILDING NAMED SHAARON  
SPECIAL SCHOOL LOCATED AT KALANGAPERI ROAD, RAJAPALAYAM**

<b>S.NO</b>	<b>DESCRIPTION OF WORKS</b>	<b>AMOUNT</b>
1	PLASTERING	178487
2	TILES WORK	123241
3	FILLING WITH GRAVEL	19560
4	CEMENT FLOORING	39120
5	WATER TANK	76790
6	COMPOUND WALL	10580
7	GRILL WORK	36000
8	WOOD WORK	87900
9	WEATHERING COURSE	68000
10	SS WORK	24000
11	ELECTRICAL	40000
12	PLUMBING	25000
13	INTERIOR WOOD WORK	60000
	<b>TOTAL</b>	<b>788678</b>
RS. 788678/- @ 790000		
<b>RUPEES SEVEN LAKH AND NINTY THOUSAND ONLY</b>		

*G. Pradeep*

**G. PRADEEP, B.E.(Civil), MBA, DLT  
Licensed Surveyor & Contractor,  
297, Sivakamipuram Street,  
RAJAPALAYAM - 626 117.**